

WELL PLUGGING RECORD

REC'D SEP 26 1957

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

McPherson County, Sec. 15 Twp. 21 Rge. 3 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW NW NW

Lease Owner Brunson Production & Exploration, Inc.

Lease Name Newfeldt B #1 Well No.

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 9-21-57 19

Plugging completed 9-24-57 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 3124' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	253'	none
				5 1/2"	3120'	2731'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 3124' and found it open. Filled w/sand to 3010' and ran 6 sacks of cement. Pulled 5 1/2" casing. Baled fluid to 245', set a 10' rock bridge and ran 15 sacks of cement. Mudded the hole to 15', set a rock bridge and ran 5 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.

I, Ralph B McLaughlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph B M Laughlin


(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of September, 19 57

Thomas V. Daggli

Notary Public.

My commission expires 9-27-58



OCT 1 - 1957
CONSERVATION DIVISION
Wichita, Kansas

BRUNSON PRODUCTION & EXPLORATION, INC.
WICHITA, KANSAS

WELL: NEUFELDT "B" #1

SW NW NW

COMMENCED RD: 8-19-57

15-21S-3W

COMPLETED RD: 8-26-57

MCPHERSON COUNTY

TOTAL DEPTH: 3120'

ELEVATION: 1441 RB

CASING: 253' 8 5/8" O.D. 28 1/2#
3120' 5 1/2" O.D. 14#CONTRACTOR: BRUNSON
PRODUCTION & EXPLORATION, INC.

STRATA	DEPTH	TOPS
Surface Soil	25	Mississippi 3023 -(1580)
Sand	140	
Shale & Clay	155	
Shale & Shells	257	
Shale & Clay	415	
Shale	420	
Anhydrite	460	
Shale	485	
Lime & Shale	785	
Red Bed	790	
Lime & Shale	910	
Broken Lime	1055	
Lime & Shale	1235	
Shale & Shells	1495	
Lime	1515	
Shale	1540	
Shale & Lime	1980	
Lime	2090	
Shale & Lime	3015	
Lime, Shale & Chert	3055	
Lime	3075	
Chert & Lime	3080	
Lime	3120	
TOTAL DEPTH	3120	

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling report.

BRUNSON PRODUCTION & EXPLORATION, INC.
BY

Ralph B. McLaughlin
Ralph B. McLaughlin-Secretary-Treas.

Signed and sworn to in my presence this 19th day of September, 1957, by Ralph B. McLaughlin, Secretary-Treasurer of Brunson Production & Exploration, Inc., a Corporation in the State of Kansas.

Anna M. Wedan
Anna M. Wedan-Notary Public

RECEIVED
STATE COMMISSION
SEP 21 1957

My commission expires July 1, 1961.

WICHITA, KANSAS

PLUGGING
FILE SEC. 15 T. 21 R. 3W
BOOK PAGE 41 LINE 6