

15-009-01447-00-00

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

BARTON County. Sec. 14 Twp. 16 Rge. (E) 13 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NE
Lease Owner E. H. Adair
Lease Name Wilborn Well No. 1
Office Address 407 W-K-H Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 20, 19 50
Application for plugging filed December 20, 19 50
Application for plugging approved December 20, 19 50
Plugging commenced December 20, 19 50
Plugging completed December 20, 19 50
Reason for abandonment of well or producing formation Barren

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough,
Producing formation Depth to top Bottom Total Depth of Well 3407 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Copy of log attached						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Placed wooden plug at 244', mixed and poured 15 sx cement on plug through drill pipe, pumped mud in hole up to 30' of surface, placed wooden plug at 30' mixed and poured 10 sx cement on plug filled surface pipe up to surface.

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to E. H. Adair Oil Company 1-25-51
Address 407 W-K-H Building
Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. H. Adair (employee of owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 19th day of January, 19 51

My commission expires September 15, 1953

23-3273-s 4-50-10M

PLUGGING
FILE SEC 14 T 16 R 32
BOOK PAGE 56 LINE 16

Notary Public.

E. H. ADAIR OIL COMPANY

Sec. 14 T. 16 R 13 W
SW SW NE
BARTON COUNTY

WILBORN

WELL No. 1

Total Depth 3407'
Comm. 12/9/50 Comp. 12/20/50

244' 8 5/8" s/casing, 130 sx.

Shale & Shells	140-244
Shale	244-950
Anhydrite	950-955
Shale & Shells	955-1520
Lime	1520-1585
Shale & Lime	1585-1714
Shale & Shells	1714-1823
Lime	1823-1934
Shale & Lime	1934-2022
Shale & Shells	2022-2050
Lime	2050-2160
Shale	2160-2170
Lime	2170-2335
Shale & Shells	2335-2512
Lime & Shale	2512-2592
Shale & Shells	2592-2672
Lime	2672-3370
Conglomerate	3370-3380
Lime	3380-3407

Certified Correct

[Signature]

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1951
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC-14 T-16 R-13W
BOOK PAGE 51 LINE 16