

15.047.00271.00.00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Edwards County. Sec. 29 Twp. 23S Rge. 20 (W)  
Location as "NE/CNW4SW4" or footage from lines C NW NW  
Lease Owner James W. Hershberger  
Lease Name Schmitt Well No. 1  
Office Address 807 1st Nat'l Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 12-30 19 63  
Application for plugging filed 12-29 19 63  
Application for plugging approved 12-29 19 63  
Plugging commenced 12-30 19 63  
Plugging completed 12-30 19 63  
Reason for abandonment of well or producing formation None

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. V. Elving  
Producing formation Depth to top Bottom Total Depth of Well 4750 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	284'	8 5/8	278'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 260', 1/2 sk. hulls  
plug & 25 sks. cement. Mud to 40', plug, 1/2  
sk. hulls & 10 sks. cement. 25 sks. cement  
for rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 8 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Terrel Drilling and Producing  
Address Box 606, Russell, Kansas

STATE OF Kansas COUNTY OF Russell, ss.  
Joe K. Branum (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum  
Box 606, Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of January, 19 64

L. Lee Simpson  
Notary Public.

My commission expires December 12, 1966

15.047.00271.00.00

W E L L L O G

OPERATOR: James W. Hershberger  
807 First Nat'l Bank Bldg.  
Wichita, Kansas

CONTRACTOR: Terrel Drilling & Producing  
Box 606  
Russell, Kansas

LEASE: Schmitt #1

COMMENCED: December 16, 1963

LOCATION: C NW NW 29-23S-20W  
Edwards County, Kansas

COMPLETED: December 30, 1963

DEPTHS & FORMATIONS

Clay w/ Streaks Sand	175	Shale		3375
Hard Cement	278	Shale & Lime		3500
Shale & Shells	675	Shale		3715
Shale w/ Sand Streaks	910	Shale & Lime		3940
Sand	1110	Shale		4045
Shale & Red Bed	1200	Lime		4130
Shale	1445	Lime & Shale		4175
Anhydrite	1482	Lime		4284
Shale & Shells	2080	Lime & Shale		4335
Shale w/ Lime Streaks	2210	Lime		4613
Shale & Lime	2303	Lime & Shale		4673
Lime & Shale	3005	Mississippi Cherty Lime		4685
Shale & Lime	3225	Chert (R.T.D.)		4750

**RECEIVED**  
STATE CORPORATION COMMISSION  
JAN 8 1964  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          )  
COUNTY OF RUSSELL) ss..

Joe K. Branum, owner of Terrel Drilling and Producing, being first duly sworn on oath says: "That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct."

Joe K. Branum  
Joe K. Branum-TERREL DRILLING & PRODUCING

Subscribed and sworn before me this 6th day of January, 1964.

L. Lee Simpson  
Notary Public

My Commission Expires December 12, 1966