


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Rice County. Sec. 23 Twp. 21 Rge. 7W (E) (W)
Location as "NE/CNW/SW" or footage from lines C N/2
Lease Owner SeRoBee Drilling Company, Inc.
Lease Name Bauer Well No. 1
Office Address 507 Union National Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed January 3, 1962 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced January 3, 1962 19
Plugging completed January 3, 1962 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Harold Hollis
Producing formation Depth to top Bottom Total Depth of Well 3415' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand from T.D. 3415' back to 3395' ran 5 sacks cement with dump bailer. Shot off and pulled 5 1/2" casing. Filled hole with mud from 3360' back to 180' set a 10' rock bridge and ran 20 sacks cement. Filled hole with mud from 110' back to 35' set a 5' rock bridge and ran 8 sacks cement back to zero. 8 5/8" surface pipe, 4' below ground level.

RECEIVED
JUN 10 1966

CONSERVATION DIVISION

6-10-66

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company
Address Box 304, Chase, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
Paul S. Seprer (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

5301 N. Broadway

(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of June, 1966

My commission expires Oct. 10, 1967

Frances H. Solomon
Notary Public.

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

15.159.06607-0000

COMP Y **Selkoe Drilling Co., Inc.**

SEC. 23 T1S R7W
LOC. 3 1/2 E3 N3

TEAM **Bauer** NO. 1

DATE 2-23-59
3415'
DEPTH 3-6-59
DRILLER **Selkoe Drilling Co., Inc.**

COUNTY



net 85/80' = 175'
rot 6 1/2' = 3407'

ELEVATION 1599'

25" Daniels Drill

Natural

FIGURES INDICATE BOTTOM OF FORMATIONS

0 -	70'	Sand
70 -	198	Red Red and Shells
198 -	215	Red Rock
215 -	640	Shale and Red Red
640 -	1015	Shale Shell Salt Line
1015 -	1150	Shells and Shale
1150 -	2400	Lime and Shale
2400 -	2660	Lime
2660 -	2720	Lime and Shale
2720 -	2791	Sand
2791 -	2885	Sandy Lime and Shale
2885 -	3284	Lime
3284 -	3401	Lime and Shale
3401 -	3406	Conglomerate
3406 -	3415	Mississippi Lime
3415		Rotary Total Depth

I hereby certify the above and foregoing to be a true and correct copy of the log on the Bauer #1, located in the Township 23 - Township 21 South - Range 7 West, Kansas.

Selkoe Drilling Co., Inc.

Paul S. Septer

sworn to before me this 2 of April, 1959.

Wanda L. L...
Notary Public