

**STATE OF KANSAS
CORPORATION COMMISSION**

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

**Information Completely
Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Blitting Building
Wichita, Kansas**

NORTH

A 4x4 grid with a small black diamond in the center. The diamond is located in the second column from the left and the second row from the bottom.

**Locate well correctly on above
Section Plat**

Stafford County, Sec. 25 Twp. 21S. Rge. 11 (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C W 20A. SW $\frac{1}{4}$ NE $\frac{1}{4}$

Lease Owner Virginia Drilling Co., Inc. et al

Lease Name Estey Well No. 1

Office Address 414 Brown Bldg., Wichita, Kansas

Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date, well completed 11-26-42 193

Application for plugging filed 11-27-42 193

Application for plugging approved 11-28-42 193

Plugging Commenced 11-28-42 193

Plugging Completed 11-28-42 193

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production.....193.....
Was permission obtained from the Conservation Division or its agents before plugging was commenced?.....**Yes**.....

Name of Conservation Agent who supervised plugging of this well. C. T. Alexander
 Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3500 Feet.
 Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 205-160 feet to 26-5 feet for each plug set.

Run drill pipe in hole to 2700 feet. Circulated with heavy mud every 500 Feet. Bridged the hole at 205 feet with wooden plug and racks. Cemented with 15 sacks cement. Filled hole with mud to 26 feet. Bridged hole and cemented with 5 sacks cement. Filling the hole to 3 feet of top.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....Virginia Drilling Co., Inc.
Address.....414 Brown Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

S. A. Murphy..... (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

414 Brown Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of December, 1942

My commission expires.....February 5, 1945.....

17-6058

10-38-5M

Notary Public.

12-5-42

Estey # 1 - C W 20A SW/4 NE/4 Sec. 25-21S-11W Stafford County, Kansas
 Company - Virginia Drilling Co. Inc et al
 Contractor - Virginia Drilling Co. Inc.
 Commenced - November 7, 1942 (Spudded)
 Completed - November 26, 1942 - Dry Hole
 Total Depth - 3500 feet.

FORMATION	DEPTH
Surface Clay	0- 20
Sand & Clay	20- 95
Reamed 40' to 11"	
Sand & Shells	40- 185
Shale & Shells	185- 205
Reamed 185-205	
Run 205' of 8 5/8 Cas.	
Sand & Shale	205- 235
Shale & Shells	235- 250
Red Bed	250- 445
Anhydrite	445- 465
Shale	465- 660
Shale & Shells	660-1025
Salt & Shale	1025-1075
Shale soft	1075-1290
Lime	1290-1310
Lime & Shale	1310-1405
Lime shells	1405-1490
Shale & Lime shells	1490-1615
Lime	1615-1700
Lime Sandy	1700-1785
Shale	1785-1800
Lime	1800-1850
Sand	1850-1860
Lime	1860-1920
Shale & Lime	1920-1950
Lime	1950-2030
Lime & sandy shale	2030-2135
Lime & shale	2135-2215
Shale & shells	2215-2315
Shale	2315-2390
Lime	2390-2465
Shale & shells	2465-2510
Lime	2510-2670
Lime w/ shale stops	2670-2725
Lime	2725-2970
Shale	2970-3073
Lime	3073-3136

Top K. C. 3090

Soft Lime	3136-3140
Lime	3140-3168

FORMATION	DEPTH
Lime soft	3168-3186
Lime	3186-3377
Cherty Conglomerate	3377-3407
Top C. Cong. 3374	
Lime	3407-3408
Sand	3408-3430
Top Simpson 3408	
Sandy Lime	3430-3445
Shale	3445-3467
Small show gas 3413	
Siliceous Lime	3467-3500

T.D. 3560 ft.
 Dry Hole

Now comes S. A. Murphy, who states that he is familiar with the drilling of oil and gas wells and that he knows personally that the Estey # 1 in C W 20A SW/4 NE/4 of Sec. 25-21S-11W Stafford County, Kansas, was drilled to a total depth of 3500 feet. Same was plugged and abandoned.

S. A. Murphy

Subscribed and sworn to before me this 4th day of December, 1942.

Murker Hooten
 Notary Public

My commission expires: February 5, 1945.

