


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County, Sec. 25 Twp. 21S Rge. 11 (W)
Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Richard C. Frick and Patricia Ann Frick, his wife.
Lease Name Frick Well No. 1
Office Address 425 Union Center
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 30, 1959
Application for plugging filed August 30, 1959
Application for plugging approved August 30, 1959
Plugging commenced August 30, 1959
Plugging completed August 30, 1959
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3480 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with mud to 240' - Set plug with hulls - 20 sacks cement through drill pipe - Fill hole with mud to 35' - Set Plug with hulls - Cap to Base of cellar with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 8 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor BERGMAN DRILLING, INC.
Address 425 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Harold Bergman (Employee or owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Bergman
425 Union Center (Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 1959

My commission expires June 30, 1963. Bevile L. Lawson Notary Public.



PLUGGING

File Sec. 25 T 21 R 11

Book Page 2 Line 10

WELL LOG

#1 Frick, NW NW SW, Sec. 25-T21s-R11w, m Stafford County, Kansas

DATE STARTED; August 17, 1959
 DATE COMPLETED: August 30, 1959

ELEVATION: 1751 K. B.

0- 192 Surface Sand & Clay
 192- 261 Shale & Shells
 261- 450 Red Bed
 450- 470 Anhydrite
 470- 565 Red Bed Shale
 565-1285 Red Bed & Shale
 1285-1490 Shale & Shells
 1490-1500 Shale - Shells
 1500-1630 Lime Shale
 1630-1820 Lime & Shale
 1820-1965 Lime & Shale
 1965-2075 Lime - Shale
 2075-2090 Shale Shells
 2090-2310 Shale
 2310-2440 Shale Lime
 2440-2470 Shale Lime
 2470-2500 Shale Lime
 2500-2655 Shale - Shells
 2655-2815 Lime & Shale
 2815-2898 Lime & Shale
 2898-2945 Lime - Shale
 2945-3060 Lime & Shale
 3060-3140 Lime & Shale
 3140-3195 Lime
 3195-3260 Lime
 3260-3315 Lime
 3315-3355 Lime
 3355-3374 Lime
 3374-3401 Lime & Chirty Conglomerate
 3401-3430 Shale & Lime Chirty
 3430-3435 Chirt Shale
 3435-3477 Lime
 3477-3480 Arbuckle
 3480 T. D.

GEOLOGICAL TOPS
 Anhydrite 450
 Heebner 2943-1192
 Toronto 2960-1209
 Douglas 2976-1223
 Iatan 3080-1329
 Lansing 3097-1346
 Base Kansas City 3362-1611
 Conglomerate 3383-1632
 Viola 3419-1668
 Simpson 3434-1683
 Arbuckle 3472-1721
 Total Depth 3480-1729

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 8 1959
 CONSERVATION DIVISION
 Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK) SS:

I, do swear that the statements and matter herein contained are true to the best of my knowledge.

BERGMAN DRILLING, INC.

Harold Bergman

 Harold Bergman

Subscribed and sworn to before me this 31st day of August, 1959.

My commission expires: June 30, 1963

Cecile L. Lawson

 Cecile L. Lawson, Notary Public

PLUGGING
 File Sec. 25 T 21 R 11w
 Book Page 2 Line 10