


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County, Sec. 24 Twp. 21 Rge. 11 (W)



Locate well correctly on above Section Plat

Location as "NE/CNW%SW%" or footage from lines NE NE NE
Lease Owner DON MOORE ASSOCIATES, INC.
Lease Name ISERN-BEVER Well No. 1
Office Address 918 CENTRAL BUILDING, WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JANUARY 2 19 64
Application for plugging filed JANUARY 2 19 64
Application for plugging approved JANUARY 2 19 64
Plugging commenced 8:30 A.M. JANUARY 3 19 64
Plugging completed 11:00 A.M. JANUARY 3 19 64
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well ARCHIE V. ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3490' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			240	8-5/8	12-22-63	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE TO 230' WITH ROTARY MUD. PUSHED 1/4 SX. HULLS AND WOODEN PLUG TO FLUID WITH DRILL PIPE. CEMENTED WITH 25 SXS. CEMENT THROUGH DRILL PIPE.
FILLED HOLE TO 40' WITH MUD. PUSHED 1/4 SX. HULLS AND WOODEN PLUG TO FLUID. CEMENTED WITH 10 SXS. CEMENT.
JOB COMPLETED @ 11:00 A.M. 1-3-64.

RECEIVED
STATE CORPORATION COMMISSION

1-7-64 JAN 7 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF BARTON, ss.
F. L. COPELAND (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. L. Copeland
925 PATTON ROAD, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 6TH day of JANUARY, 19 64

My commission expires JANUARY 16, 1967

Reva C. Brown
REVA C. BROWN Notary Public.



DRILLER'S LOG
ISERN-BEVER

COMPANY: DON MOORE ASSOCIATES, INC.
 CONTRACTOR: WESTERN PETROLEUM CO., INC.
 COMMENCED: DECEMBER 21, 1963
 COMPLETED: JANUARY 3, 1964
 DESCRIPTION: NE NE NE
 SECTION 24-T21S-R11W
 STAFFORD COUNTY, KANSAS

ELEVATION: 1732 DF
 1734 KB
 CASING RECORD: 8 JTS. 8-5/8"
 28# CASING
 TOTAL DEPTH: 3490'

RECEIVED
 STATE CORPORATION COMMISSION

JAN 8 1964

CONSERVATION DIVISION
 Wichita, Kansas

FORMATION	FROM	TO	REMARKS
CLAY SAND	0	60	RAN 8 JTS. 8-5/8" 28# USED PIPE. OVER-ALL TALLY 231.95'. SET @ 240'. CEMENTED WITH 260 SXS. COMMON CEMENT, 2% GEL, 3% C.C. PLUG DOWN @ 8:00 P.M. 12/21/63. CEMENT CIRCULATED.
SAND	60	170	
RED BED	170	230	DST #1, 3327-57'. OPEN 1 HOUR. WEAK STEADY BLOW. RECOVERED 85' WATERY MUD WITH SMALL SHOW OIL. IBHP 1170#, FBHP 1130#, IFP 0#, FP 35#/30", IHH 1840#, FHH 1820#.
SHALE	230	252	
RED BED	252	415	DST #2, 3376-3386'. OPEN 1 HOUR. WEAK BLOW FOR 24 MINS. RECOVERED 22' MUD, IBHP 1110#/30", FBHP 745#/30", FP 0#, HH 845#.
ANHYDRITE	415	435	
SHALE & SHELLS	435	1450	DST #3, 3386-3400'. STRONG BLOW DECREASING TO FAIR. OPEN 1 HOUR. RECOVERED 2590' FORMATION WATER. IBHP 1180#, FBHP 1180#/30", IFP 440#, FFP 1135#, HH 840#.
LIME & SHALE	1450	2230	
SHALE & LIME	2230	2440	WIRE LINE TEST #1, 3304-06 1/2' MARMATON. OPEN 2 HOURS. RECOVERED 4400 CC WATER, RESISTIVITY .055 (FILTRATE). IBHP 1375#/60", FBHP 1350#/25".
LIME-SHALE	2440	2656	
LIME	2656	2792	LOGGED BY SCHLUMBERGER. D & A 1-3-64
LIME & SHALE	2792	3030	
LIME	3030	3357	
LIME & CHERT	3357	3400	
SHALE	3400	3405	
SHALE & LIME	3405	3439	
LIME & SHALE	3439	3490	
RTD	3490		
<u>ELECTRIC LOG TOPS</u>			
ANHYDRITE	412	1322	
LANSING	3062	-1328	
VIOLA	3348	-1614	
SIMPSON	3378	-1644	
ARBUCKLE	3442	-1708	


STATE OF KANSAS)
 SS
 COUNTY OF BARTON)

I, THE UNDERSIGNED, BEING DULY SWORN ON OATH, STATE THAT THE ABOVE STATEMENT AND LOG ARE TRUE AND A CORRECT RECORD AND LOG OF THE WELL DRILLED AT THE LOCATION ABOVE DESCRIBED.

WESTERN PETROLEUM CO., INC.

F. L. Copeland
 F. L. COPELAND, DRILLING SUPT.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 6TH DAY OF JANUARY, 1964



Reva C. Brown
 REVA C. BROWN, NOTARY PUBLIC

MY COMMISSION EXPIRES JANUARY 16, 1967