

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

FORMATION PLUGGING RECORD

**Strike out upper line
when reporting plug-
ging off formations.**

Range ^{NORTH} 9TH West

Rice County. Sec. 22 Twp. 21S Rge. 9E 9 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C SE $\frac{1}{4}$ NW $\frac{1}{4}$

Lease Owner. SHARON DRILLING COMPANY, Inc.

Lease Name. Small Well No. 1

Office Address. 352 No. Broadway Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed. April 7 19 41

Application for plugging filed. December 6 19 45

Application for plugging approved. December 11 19 45

Plugging commenced. March 12 19 46

Plugging completed. March 18 19 46

Reason for abandonment of well or producing formation. Gas depleted

If a producing well is abandoned, date of last production August 19 45
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruell Durkee
Producing formation Misener Depth to top 3313 Bottom 3355 Total Depth of Well 3363 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Mud	3363	to	150
Cement	150	to	110
Mud	110	to	10
Cement	10	to	Cellar base

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Sharon Drilling Company, Inc.
Address 352 No. Broadway Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
M. S. Davis (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well as filed and that the same are true and correct. So help me God.

NOT SIGNED OR NOTARIZED ✓ (Signature) M. D. Davis
352 No. Broadway, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of April, 1946

My commission expires Sept. 16, 1948

15.159-19367-0002

Sharon Drilling Co. #1 Small

Initial Potential 3,962,000
Rock Pressure 913

Con SE NW 22-21-9W, Rice Co. Casings:
 8" 100'
 4 1/2" 3313'
 Commenced: 2-25-41
 Completed: 3-27-41
 T. D. 3323 1/2

L O G

Sand	40
Red Rock	99
Red Rock	250
Anhydrite	270
Shale & shells	5910
Salt & shale	1080
Shale & shells	1135
Anhydrite & lime	1160
Shale & lime	1470
Sandy lime	1524
Shale & lime	1650
Broken lime	1750
Lime	1785
Lime & red rock	1800
Shale & shells	1920
Shale	2160
Lime & shale	2330
Shale	2485
Lime	2500
Shale	2565
Lime	2725
Broken lime	2835
Shale & shells	2982
Lime	3248
Shale & shells	3313
Misener Sand	3314

Cable Log

Sand 3314-3323 1/2
 Gauged 3,718,000 gas before perforated

Perforated 24 shots 3313-3323
 Gauged 3,838,000 gas after perforating

Deepened

I.P. 15 BO to 1/2 Million Gas
 T D 3338
 Commenced 5-20-44
 Completed 6-6-44
 Sand 3323 to 3326 increase in gas
 Sand 3326 to 3333 show of oil
 Sand 3333 to 3338 increase in oil
 Gauged 814,000 gas at 3331
 " 814,000 " " 3333
 " 814,000 " " 3338
 Well started spraying oil at 3335
 Sprayed 30 gallons of oil per hour at 3338

5-24-44

Shot 20 qt. 3322 to 3336
 Cleaned out hole, swabbed to bottom and
 swabbed down
 Swabbed 4 1/2 BOPH for 4 hr. on 5-29-44

Put on pump and wouldn't pump
 Flow 10 to 15 BOPD and 1/2 million feet of gas

Deepened Well

I.P. 1/2 Million gas and 5 to 10 BOPD
 T.D. 3363
 Commenced 9-18-44
 Completed 10-9-44

L O G

Sand 3338-3355
 Maquoketa dol 3355-3363 TD
 No increase in gas, oil, no water
 9-25-44 Shot 60 qt. from 3320-3363
 No increase in oil or gas.

APR 9 - 1946

22 21 90
 35 36