

Sharon Drilling Company, Inc.,

No. 1 Currie,

NW SW NE $\frac{1}{4}$ 22-21-9W.,
Rice County, Kansas

Operations Commenced: August 11, 1944
Well Spudded: August 14, 1944
Rotary Completion: August 28, 1944
Rotary Total Depth: 3336'
Cable Tool Completion: ~~August~~ ^{SEPT} 15, 1944
Cable Tool Total Depth: 3478'

Elevation: 1672'
Potential: Dry

Acid in K. C. - 500 Gal and 2000 Gal. 40 Qt. Shot in Misener 3339-66
Contractor: Sharon Drilling Company, Inc.

CASING RECORD

105' of 8 5/8" Surface Casing cemented w/125 sacks cement.
3331' of 5 1/2" O. D. 14# Casing cemented w/125 sacks cement.

DRILLERS LOG

Sand	0	To	46
Red Bed			243
Anhydrite			260
Shale & Shells			740
Salt & Shale			980
Shale & Shells			1275
Broken Lime			1815
Shale			1830
Broken Lime			1855
Shale & Shells			2240
Shale & Lime			2315
Shale & Shells			2395
Shale & Lime			2450
Sandy Shale			2493
Lime			2848
Shale			2858
Lime			2898
Shale			2923
Lime			3052
Soft Lime			3065
Lime			3278

Shale & Lime Shells	3325
Shale	3331
Shale Sand	3334
Sand (Rotary T. D.)	3336
Sand	3366
Lime	3464
Sand	3474
Water Sand (T. D.)	3478

GEOLOGICAL TOPS

Topeka	2493'
Heebner	2791
Base Oread	2844
Brown ls	2923
Lansing	2954
Spongy fossiliferous soft ls. pin point porosity excellent odor & rainbow 3000-03	
Oolitic porous no shows	3052-63
Base Kansas City	3267
Misener Sand	3331
Maoketa limey dolomite	3366
Viola Lime	3408
Simpson Shale	3464
Simpson sand	3465
HFW in Simpson sand	3474-78

P. B. to 3366
Shot 40 Qt. solidified 3339-66
1/4 bailer oil & 1 1/3 bailer
Wtr. P. H., and show of gas.
Gravity of oil 35
Perforated 12 shots 3325-36,
no increase.
Set Land-Wells plug 3050
Perforated 62 shots 2989-3074-no show
500 Acid - show free oil.
Reacidized 2000 Gal - no increase in oil.

PLUGGING

22 21 910
135 34