

15-159.19171.0001

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

KCC PKT 01 PerCP-13 11-16-06

Lease Operator: Southern Star Central Gas Pipeline Address: 4700 Highway 56 P.O. Box 20010 Owensboro, Kentucky Phone: (270) 852-4490 Operator License #: 33097

API Number: 15-159-19171-00-02 Lease Name: Alden Gas Storage - PKT perCP-13 Well Number: 0-13

Type of Well: Gas Storage Observation Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): NW-SW-SW-SW 395' 340' 20' Feet from North / South Section Line 5003' Feet from East / West Section Line Sec. 225104 Twp. 21 S. R. 9 East West

The plugging proposal was approved on: 7/25/2006 (Date) by: Doug Louis (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, Is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Kansas City Ls. Obs. Well Depth to Top: 2439' Bottom: 2661' T.D. 3333' Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

County: Rice Date Well Completed: 11-20-1937 8-6-60 Plugging Commenced: 9/5/2006 Plugging Completed: 9/6/2006

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes entries for Kansas City Ls. saltwater and surf.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plug back from 3333'-2930' on 10-6-1980 with 445 sks. On 9-5-2006 ran 2 3/8" tubing to 2700' and pumped 75 sks., spotted drilling mud, and pumped another 75 sks. On 9-6-2006, shot 7" casing at 1900' and pulled casing out of hole. Ran back in hole with 2 3/8" tubing to 1900' and pumped 50 sks., pumped 75 sks. at 1200', pumped 75 sks. at 750', pumped 200 sks. from 500' to surface. The well was capped and buried 5" below surface.

Site reclaimed.

Name of Plugging Contractor: Gressel Oilfield Service Inc. Kings Well Service License #: 3904 33728 Address: P.O. Box 607 Burrton, Kansas 67020

Name of Party Responsible for Plugging Fees: Southern Star Central Gas Pipeline

State of Kentucky County, Daviess, ss.

D. Mark Rouse Staff Geologist

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) D. Mark Rouse 5566P

(Address) 4700 Hwy. 56 Owensboro, Ky. 42304

SUBSCRIBED and SWORN TO before me this 30th day of October 2006

Shelley A. Rouse My Commission Expires: 10-30-2009

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED NOV 03 2006

KCC WICHITA