

APL. NUMBER 15.159.30211.0000

LEASE NAME SW Tobias L-Kc Unit

WELL NUMBER #2

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 3 TWP. 21 RGE. 9 (E) or (W)

COUNTY Rice

Date Well Completed 6-9-66

Plugging Commenced 6-13-90

Plugging Completed 7-2-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Aspen Drilling Company

ADDRESS Box 783, Great Bend, Ks. 67530

PHONE # (316)-792-2469-792-2080 OPERATORS LICENSE NO. 5708

Character of Well 5708

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 28, 1990 (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached? With application

Producing Formation Depth to Top Bottom T.D. 3010'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				7"	257'	None
				4-1/2"	3009'	1,159.38'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Allied squeezed bottom with 25 sacks down 4-1/2" displaced to 2600'. Shot casing at 1162' Pulled 37 joints of 4-1/2" casing. Allied plugged well with 35 sacks at 1162' 35 sacks at 700 and 70 sacks circulated to surface at 300' and used to cap well.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530 7-9-90

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Aspen Drilling Co. JUL - 9 1990

STATE OF Kansas COUNTY OF Barton

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 6th day of July, 1990

Iona M. Leatherman
 Notary Public

My Commission Expires:
