


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rice County, Sec. 3 Twp. 21 Rge. 9 (E) (W)
Location as "NE/CNWKSWK" or footage from lines. C SW SW SW
Lease Owner Phoenix Drilling Company
Lease Name Werner Unit #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 8/3/70 19
Plugging completed 8/5/70 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation Depth to top Bottom Total Depth of Well 3029 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	208	none
				4 1/2	3030	2588'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3029', ran sand to 2950' and dumped 3 sacks of cement. Loaded hole, shot pipe at 2650', 2587', worked pipe loose and pulled 80 joints. Bailed fluid to 205', set 10' rock bridge and dumped 25 sacks of cement. Mudded to 40', set 10' rock bridge and dumped 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1970
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct: So help me God.

(Signature) [Signature]
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of August, 19 70

My commission expires 2/15/71

[Signature]
Notary Public.

ORIGINAL

RECEIVED
 AUG 10 1968


SEC. 3 T. 21 N. 9W
 LOC. C SW SW

COMPANY DEAN & CLARK & ASPEN DRIG.
 FARM Werner Unit NO. 1

TOTAL DEPTH 3030
 COMM. 10-27-67
 SHOT OR TREATED
 CONTRACTOR Isern Drlg.
 ISSUED 8-10-68

COMP. ~~11-1-67~~

COUNTY Rice



RECEIVED
 JUL 9 1970
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas

CASINO
 20 10 5/8" @ 208' w/185 SX
 15
 12 6 4 1/2" @ 3029' w/75 SX
 13 5'

ELEVATION 1681' KB

PRODUCTION DRY/LANS

FIGURES INDICATE BOTTOM OF FORMATIONS

ELEVATION: 1677GL'; 1679' DF; 1681' KB.

Figures indicate bottom of formation:

PIPE RECORD:
 8 5/8" set @ 208' with
 185 sacks cement.
 4 1/2" set @ 3029' with
 75 sacks cement.

0	to	65	sand
		209	red rock
		251	shale & red bed
		650	red bed & shale
		1370	shale & shells
		1860	lime & shale
		2490	shale & shells
		2550	lime & shale
		2625	lime
		2810	lime & shale
		2852	shale & lime
		3030	lime & shale
		3030	Rotary Total Depth

ROTARY COMMENCED: 10-27-67.
 ROTARY COMPLETED: ~~11-1-67~~ 6-20-68

FOPS:
 Anhydrite 251
 Base Anhydrite 274
 Heebner 2780
 Iron Lime 2913
 Kansas City 2942

*Log 2696
 Log 2812*

STATE OF KANSAS)
 COUNTY OF BARTON) SS

I, Dean Wells, Partner of Isern Drilling Company, Contractor for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

Dean Wells
 Dean Wells, Partner

Subscribed and sworn to before me on this 8th day of November, 1967.

George A. Meyer
 George A. Meyer, Notary Public

My commission expires: February 10, 1971.

COPY