

STATE OF KANSAS
STATE CORPORATION COMMISSION

15. 047. 00003. 00. 60


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Edwards County, Sec. 13 Twp. 23S Rge. 20 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Prime Drilling Company & Westpan Hydrocarbon Co.
Lease Name Ploger-Smith Well No. 1
Office Address 814 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 12 19 57
Application for plugging filed July 12 19 57
Application for plugging approved July 12 19 57
Plugging commenced July 12 19 57
Plugging completed July 12 19 57
Reason for abandonment of well or producing formation no oil in commercial quantities found

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4878 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	257	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth (4878') to 250'. Set Plug #1 with 20 sacks cement. Filled hole with extra heavy rotary mud from Plug #1 to 35'. Set Plug #2 at 35' cemented with 10 sacks cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Prime Drilling Company
Address 814 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss:
R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. McNicol
814 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of July, 19 57

My commission expires September 30, 1959

Darlene May
Darlene May
Notary Public.

PLUGGING
FILE SEC. 13 T. 23 R. 20W
BOOK PAGE 27 LINE 30

RECEIVED
STATE CORPORATION COMMISSION
7-18-1957
JUL 18 1957
CONSERVATION DIVISION
Wichita, Kansas

15.047.00003.00.00

ROTARY DRILLING LOG

OPERATOR: Prime Drilling Company &
Westpan Hydrocarbon Co.
PLOGER-SMITH NO. 1
SE SE SE Sec. 13-23S-20W,
Edwards County, Kansas

CONTRACTOR: Prime Drilling Company
COMM: 6-24-57
COMP: 7-12-57

Remarks: Set 8-5/8" surface casing at
257' cemented with 185 sacks Pozmix
2% C.C.

Formations:

Clay & Shale	40'
Shale & Shells	160'
Sandy Shale	180'
Shale & Shells	258'
Sand Shale	850'
Sand	950'
Shale, Sand & Red Bed	1150'
Red Bed, Red Rock & Shale	1450'
Red Rock & Shale	1660'
Shale & Shells	1915'
Sandy Shale & Shells	2215'
Shale & Shells	2240'
Shale & Lime	2425'
Sandy Lime & Shale	2490'
Lime & Shale Sandy	2575'
Sandy Lime & Shale	2665'
Lime & Shale	2700'
Lime	2870'
Lime & Shale	3596'
Lime	3970'
Shale Sand & Lime	4020'
Lime	4600'
Lime & Chert	4615'
Chert & Sand	4649'
Chert & Lime	4657'
Shale & Lime	4676'
Lime	4689'
Sand	4704'
Sand & Lime	4725'
Lime Chirty	4776'
Cherty Lime	4878'

Rotary Total Depth (D&A) 4878'

We certify the above log is true and
correct to the best of our knowledge
and belief.

PRIME DRILLING COMPANY

R. R. McNicol

R. R. McNicol

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING			
FILE	SEC	T	R
	13	23	20W
BOOK	PAGE	LINE	
	27	30	