

15.047.10077.00.00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Edwards County, Sec. 6 Twp. 23S Rge. (E) 20(W)

Location as "NE/CNW%SW%" or footage from lines NW SW NW
Lease Owner Natural Gas & Oil Corp and Republic Natural Gas
Lease Name Jensen Well No. 1
Office Address 1009 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed April 9, 1954 19
Application for plugging filed (orally) April 9, 1954 19
Application for plugging approved " April 9, 1954 (4/12/54 written)
Plugging commenced April 9, 1954 19
Plugging completed 4 PM April 9, 1954 19
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	212	10 3/4"	212	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 4876 T.D to 275 feet
Set plug at 275' and ran 25 sacks cement to 225 feet
Filled hole with heavy mud from 225 feet to 25 feet
Set plug and capped with 15 sacks cement to cellar.

4-15-54

RECEIVED
WICHITA, KANSAS
DIVISION

Name of Plugging Contractor Drilling Department of Natural Gas and Oil Corporation
Address Route #1, Great Bend, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.
Claud Sheats (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God!

(Signature) Claud Sheats
1009 Central Building, Wichita, Kans
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April 1954

Esther Small
Notary Public.

My commission expires May 25, 1957



DRILLER'S LOG

COMPANY: Natural Gas and Oil Corporation
and
Republic Natural Gas Company

FARM: Jensen #1, NW SW NW Sec. 6-23S-20W
Edwards County, Kansas

COMMENCED: March 18, 1954

COMPLETED: April 9, 1954

ELEVATION: 2310 RB

0	to	45	Clay and sand
45	to	160	Shale
160	to	250	Shale and shells
250	to	435	Red bed and shells
435	to	840	Shale and shells
840	to	980	Sand
980	to	1408	Red bed and shale
1408	to	1430	Anhydrite
1430	to	1445	Shale and anhydrite
1445	to	1745	Shale and shells
1745	to	2200	Lime and shale
2200	to	2220	Shale
2220	to	2965	Lime
2965	to	3045	Lime and shale
3045	to	3150	Lime
3150	to	3375	Lime and shale
3375	to	3770	Lime
3770	to	3800	Lime and shale
3800	to	3903	Lime
3903	to	3954	Lime and shale
3954	to	4390	Lime
4390	to	4430	Lime and shale
4430	to	4498	Lime
4498	to	4518	Diamond cored
4518	to	4530	Chert
4530	to	4579	Chert and shale
4579	to	4613	Lime and shale
4613	to	4626	Sand
4626	to	4648	Lime and shale
4648	to	4725	Lime
4725	to	4748	Lime and chert
4748	to	4770	Lime
4770	to	4800	Lime and chert
4800	to	4876	Lime
		4876	T.D.

STATE CORP.

Set 211 ft 10 3/4" 32# surface pipe. Cemented with 200 sacks cement and 3 sacks calcium chloride.

Dored 4498 to 4518, hard chert, broke core bit, slight stain, no porosity.

DST #1 4581-4621, open 1 hr, SI 30 min, weak blow, rec. 120' watery mud, 0# IFP, 0# FFP, BHP 1350#.

DST #2 4838-76, open 1 hr, SI 30 min, weak blow 1 hr, rec. 125 ft muddy salt water, 0# IFP, 0# FFP, 1420# BHP.

TOPS:

Anhydrite	1408	Lansing	3948	Simpson	4821
Heebner	3858	Miss.	4497	Arbuckle	4835
Brown Ls	3937	Viola	4626		

Ran Schlumberger

DRY, PLUGGED AND ABANDONED

PLUGGING
FILE SEC 6 23.2 200
BOOK PAGE 26 LINE 1

15.047-10077.00.00

ACKNOWLEDGMENT

I, Claud Sheats, do hereby certify that the above and foregoing is a true and correct copy of the log of the Jensen #1, NW SW NW Section 6-23S-20W, Edwards County, Kansas, as reflected by files of the Natural Gas and Oil Corporation.


Claud Sheats, Regional Geologist

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 14th day of April, 1954.


Esther Unsell, Notary Public

My commission expires May 25, 1957.

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1954
CONSERVATION DIVISION
Wichita, Kansas