


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Edwards County. Sec. 18 Twp. 23S Rge. (E) 19 (W)
 Location as "NE/CNW/SW" or footage from lines. NW NW NE
 Lease Owner C. U. Bay
 Lease Name Lippoldt Well No. 1
 Office Address Box 513 Chase Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed Dec. 7 19 53
 Application for plugging filed Dec. 14 19 53
 Application for plugging approved (oral) Dec. 7 19 53
 Plugging commenced Dec. 7 19 53
 Plugging completed Dec. 7 19 53
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Hives Pratt Kansas
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4975 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	239'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole from TD. 4975' to 2404'.
Set plug at 2404' and cemented w/20 sax cement.
Mudded hole to 40'.
Set plug at 40' and cemented w/10 sax cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glen R. Nye Drilling Co.,
 Address Drawer # 30, Hays Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Forrest Crawford (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Forrest Crawford
 (Address) _____

SUBSCRIBED AND SWORN TO before me this 14 day of December, 19 53

My commission expires May 20 1954
Vincent O. Gray Notary Public

PLUGGING
 FILE SEC. 18 T. 23 R. 19W
 BOOK PAGE 142 LINE 36

12-15-53

15.047.00095.00.00

COMPANY: C.U. Bay FARM: Lippoldt # 1
 CONTRACTOR: Glen R. Nye Drilling Co. LOCATION: NW NW NE Sec.18-23S-19W
 COMMENCED: November 14 1953 Edwards County Kansas
 COMPLETED: December 6 1953 CASING RECORD: 8 5/8" set at 239'
 Dry and abandoned
 ELEVATION: 2227' DF

cellar	5
surface soil & clay	45
sand	60
sandy shale & gumbo	140
sand	155
gumbo clay	180
sand	190
clay & gumbo	215
red bed	225
shale	240
blue shale	300
shale & clay	335
shale & clay & sand streaks	560
shale, red bed, & sand streaks	650
red bed & shale	695
anhydrite streak	705
red bed	815
sand	940
red bed	1320
red bed & shale	1360
anhydrite	1382
red bed & shale	1510
shale & shells	1660
shale & shells	1800
shale & lime streaks	1875
shale & lime streaks	2080
shale & lime	2345
lime and shale	2457
lime and shale	2590
lime and shale	2665
lime and shale	2755
lime and shale	2820
lime and shale	2905
lime and shale	3005
lime and shale	3080
shale and lime	3180
shale and lime	3280
shale and lime	3346
shale and lime	3450
shale and lime	3545
shale and lime	3627
lime and shale	3684
lime, shale and sand streaks	3756
lime and shale	3828
lime and shale	3884
lime and shale	3955
lime and shale	3991
lime	4039
lime and shale	4093
lime and shale	4130
lime and shale	4184
lime and shale	4251
lime and shale	4300
lime and shale	4339
lime and shale	4395
lime and shale	4445
lime and shale	4477
lime and shale	4531
chert	4536
chert	4546

Top Heebner 3860' (-1628)
 Top Toronto 3882' (-1640)
 Brown Lime 3953' (-1721)
 Top Lansing 3965' (-1733)

PLUGGING
 FILE SEC 18 T 23 R 19W
 BOOK PAGE 147 LINE 36

chert	4554
chert	4566
chert	4594
lime and shale	4637
lime & shale and chert	4655
cherty lime and shale	4688
chert & lime	4702
chert, lime and shale	4740
cherty lime	4765
cherty lime, and shale	4796
cherty lime, and red shale	4825
cherty lime, and shale	4860
lime, shale and sand	4881
simpson	4900
shale and lime	4932
arbuckle	4975 TD.

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

GLEN R. NYE DRILLING CO.

By (S) Glen R. Nye

STATE OF KANSAS)
) ss
ELLIS COUNTY)

Subscribed to and sworn to before me, a notary public, in and for said County and State this 8th day of Dec. 1953

(S) John L. Spiess
Notary Public

My commission expires May 2 1957

COPY