


Give All Information Completely  
Make Required Affidavits  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rice County. Sec. 22 Twp. 21 Rge. 7 (XX) (W)

Location as "NE/CNW/SW" or footage from lines SW SE  
Lease Owner Wofford Oil Company  
Lease Name Berniece Warnock Well No. 1  
Office Address 1258 Cleveland-Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 12 19 67  
Application for plugging filed September 12 19 67  
Application for plugging approved September 12 19 67  
Plugging commenced September 12 19 67  
Plugging completed September 12 19 67  
Reason for abandonment of well or producing formation Dry and No Oil

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 180 feet. Set cement plug at 180 with 25 sacks cement. Set top plug at 40 feet with 15 sacks cement. Plgd rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 13 1967

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Henry Wofford Drilling Company, Inc.  
Address 1258 Cleveland Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Henry L. Wofford (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] 1258 Cleveland-Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of November, 19 67

My commission expires 4-27-71

[Signature] Glenda C. Fountaine  
Notary Public.

## WELL LOG

Drilling Contractor: Henry Wofford Drilling Company, Inc.,  
 Drilling Commenced: September 1, 1967  
 Drilling Completed: September 12, 1967  
 Wofford Oil Company : # 1 Warnock  
 SW SE Section 22, Township 21, Range 7 West-Rice County, Kansas  
 Elevation: 1608 K.B.  
 Surface Pipe: 13 3/8" at 213 feet . Cemented with 200 sacks cement.

## FORMATION SUMMARY

0 - 213	Sand-surface soil
213-850	Shale, Red bed, salt
850-1260	Shale
1260-1350	Lime Shale
1350-1370	Sand
1370-1450	Lime Shale
1450-1700	Lime-Shale
1700-2035	Lime & Shale
2035-2180	Shale-Shells
2180-2400	Shale
2400-2525	Shale & Lime
2525-2600	Lime & shale
2600-2695	Lime
2695-2725	Lime & shale
2725-2790	Shale
2790-2890	Shale & lime
2890-2899	Shale & Lime
2899-2950	Lime & Shale
2950-3300	Lime & shale
3300-3409	Lime & shale
3409-3420	Mississippi formation
Rotary Total Depth	3420

NOV 13 1967  
 NOV 13 1967  
 NOV 13 1967