


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Rice County, Sec. 20 Twp. 21 Rge. 7 (E) (W)  
Location as "NE/CNW/SW" or footage from lines. C NE NW  
Lease Owner Sterling Drilling Company  
Lease Name Mansz #3 East Well No.  
Office Address Sterling, Kansas 67579  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 6/1/72 19  
Plugging completed 6/3/72 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman  
Producing formation Depth to top Bottom Total Depth of Well 3444 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	173	none
				5 1/2"	3429	3008'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3444' and ran sand.. Had to run sand again to 3400' and ran 5 sacks of cement. Shot pipe at 2990' and pulled 94 joints of 5 1/2". Set rock bridge at 215', ran 35 sacks of cement. Mudded to 40' and set rock bridge and ran 10 sacks of cement on top.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 9 1972 6-9-1972

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
KNIGHT CASING PULLING CO., INC.

Name of Plugging Contractor  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of June, 1972

My commission expires



MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

[Signature]  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 23 1972

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579CONSERVATION DIVISION  
Wichita, KansasWELL LOG ----- MANSZ ESTATE #3  
Located: C NE NW, Section 20-21S-7W, Rice County, KansasOWNER: Sterling Drilling Company and Martin Oil and Gas Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling CompanyCOMMENCED: September 5, 1971  
COMPLETED: September 10, 1971

TOTAL DEPTH: 3430'

LOGCASING RECORD

0 - 70	Sand	Ran 4 joints 8 5/8" casing, 161.08' cemented at 173' K.B. with 160 sacks 60/40 Pozmix with 3% HA5. Plug down at 2:00 PM, 9-5-71.
70 - 177	Shale	
177 - 1065	Shale and Red Bed	
1065 - 2690	Lime and Shale	
2690 - 3430	Lime	Ran 108 joints 5 1/2" 14# 8rd casing, 3419.23' threads off, tested 4000#, set at 3429' with 75 cu. ft. salt saturated cement. Plug down 2:00 PM, 9-10-71.