


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027

Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Rice County, Sec. 20 Twp. 21 Rge. 7W (E) (W)  
Location as "NE/CNW/SW" or footage from lines: C N/2 S/2 (C NESE)  
Lease Owner: Sterling Drilling Company  
Lease Name: Bennett #1 Well No.:  
Office Address: Sterling, Kansas 67519  
Character of Well (completed as Oil, Gas or Dry Hole):  
Date well completed: 19\_\_\_\_  
Application for plugging filed: 19\_\_\_\_  
Application for plugging approved: 19\_\_\_\_  
Plugging commenced: 6/13/73 19\_\_\_\_  
Plugging completed: 6/16/73 19\_\_\_\_  
Reason for abandonment of well or producing formation: depleted.

If a producing well is abandoned, date of last production: 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well: Scott  
Producing formation: Depth to top: Bottom: Total Depth of Well: 3427 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	181	none
				5 1/2"	3426	2949'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3438', ran sand to 3400' and dumped 5 sacks cement. Loaded hole, shot pipe at 3015', 2952', pulled 95 joints. Could only bail fluid down to 20'. Pumped 3 sacks hulls, 20 sacks gel and 100 sacks 50-50 pos-mix.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 21 1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor: KELSO CASING PULLING  
Address: CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of June, 1973

My commission expires \_\_\_\_\_  
MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

Margaret Melcher  
Notary Public.

15.159.20446-0000

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 21 1973  
CONSERVATION DIVISION  
Wichita, Kansas

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- BENNETT #1

Located: E/2 SE/4, Section 20-21S-7W, Rice County, Kansas

OWNER: Sterling Drilling Company, Cardinal Petroleum Company, N. L. Koin  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 23, 1972

COMPLETED: September 27, 1972

TOTAL DEPTH: 3427'

LOG

CASING RECORD

0 - 68	Sand and Gravel
68 - 1000	Shale
1000 - 1165	Salt and Shale
1165 - 2530	Shale and Lime
2530 - 2860	Lime
2860 - 3155	Lime and Shale
3155 - 3418	Lime
3418 - 3427	Lime and Chert

Ran 8 5/8" surface casing 1.69 - 47'  
cemented at 181' K.B. with 185 sacks 60/40  
Pozmix, 3% HA-5. Plug down at 3:00 PM,  
9-23-72.

Ran 111 joints 5 1/2" 14# J-55 casing,  
8rd tested 4000#, 3435.63' threads off,  
set at 3426' with 75 cu. ft. salt  
saturated cement. Plug down 3:30 PM,  
9-27-72.