

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

JAN 11 1983

Form CP-4
Rev. 12-15-80

CONSERVATION DIVISION
Wichita Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rice SEC. 20 TWP. 21 RGE. 7w E/W
Location as in quarters or footage from lines:
NE NE SE

Locate Well
correctly on above
Section Platt.

Lease Owner Sher Lon Corp.
Lease Name Heter Well No. 1
Office Address 320 South Broadway, Sterling Ks. 67579
Character of Well (Completed as Oil, Gas or Dry Hole): oil
Date Well Completed 6/10/82
Application for plugging filed 11/14/82
Plugging commenced 12/31/82
Plugging completed 1/7/83
Reason for abandonment of well or producing formation Dry

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation KC. Depth to top _____ bottom _____ T.D. 3500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surface	0	234	8 5/8		
		0	3499	5 1/2		2547

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Sand back to 3400 and dump 5 sx. cement

Set bridge at 300 ft. and filled to bottom of cellar with
4 1/2 yards of readymix cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Nicholas Casing Pulling
Box 206 Geneseo Kansas 67444

STATE OF Kansas COUNTY OF Rice, ss.
G. A. Nicholas (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) G. A. Nicholas
(Address) _____

SUBSCRIBED AND SWORN TO before me this 10th day of January, 19 83


Toni L. Prickett
Notary Public.

My Commission expires: December 25, 1984



Permit #
operator license 5994

15-159-21065-0000

S. 20 T. 21 R. 7 ^W W
 Loc. NW NW SE
 County Rice
 640 Acres
 N

 Elev.: Gr. 1611
 DF 1613 KB 1616

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 159 — 21065
 County Number

Operator
 SHER-LON CORPORATION

Address
 320 S. Broadway - Sterling, KS 67579

Well No. #1 Lease Name Heter

Driller
 Tom Kesselowski

Spud Date 1-11-81 Date Completed 1-19-81 Total Depth 3500 P.B.Y.D.

Directional Deviation Oil and/or Gas Purchaser Derby

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Fresh water Protection	12-1/4	8-5/8	24#	234'	Reg Portland	200	2% gel 3% cc
Production	7-7/8	5-1/2	15#	3499	70% Reg. Portland 30% Poz mix	70 30	10% salt

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
3	.47	3459-75

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8	3472	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
30,000 LBS 10/20 sand 71,000 Gal. water & 2500 Gal.	3459-75

STATE GEOLOGICAL SURVEY
 RECEIVED
 OCT 06 1982
 CONSERVATION DIVISION
 WICHITA, KANSAS

INITIAL PRODUCTION

Date of first production 3-29-81 Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS
 Oil 5 bbls. Gas MCF Water loadwater bbls. Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) used Producing interval (s) 3459-75

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.