


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pawnee County, Sec. 31 Twp. 21 Rge. 18W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW NW NE  
Lease Owner Bennett & Roberts Drilling Co.  
Lease Name FOX Well No. 1  
Office Address Drawer 633, Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 6/24 19 56  
Application for plugging filed Verbal 6/24 19 56  
Application for plugging approved Verbal 6/24 19 56  
Plugging commenced 6/24 19 56  
Plugging completed 6/24 19 56  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege, Box 283, Hoisington, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4539 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	977'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled to 300' w/ heavy mud 1/2 sack Hulls &  
Wooden plug, 20 sacks Cement. Mud up to 35',  
1/2 sk Hulls, plug on wire, 10 sks Cement down  
8 5/8" casing.

6-3-56

RECEIVED

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst  
Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 27th day of June, 19 56  
Mildred Notary Public.

My commission expires May 7, 1960

PLUGGING  
FILE SEC 31 T 21 R 18W  
BOOK 74 LINE 27

Bennett & Roberts Drilling Co.  
Fox #1

NW NW NE Sec. 31-21-18W  
Pawnee County, Kansas

R.T.D. 4539

Commenced 6/9/56  
Completed 6/24/56

Casing Record  
8 5/8" Set @ 977' w/475 sx cmt.

----- -Figures Indicate Bottom of Formation-----

Surface Clay	20'
Sand	75
Sandy Shale	120
Sand	185
Shale, Sand Rock	245
Shale, Blue & Gray	440
Sand	475
Red Bed, Shale	535
Shale, Lime Shells	580
Red Bed & Shale	670
Red Bed (Sandy Shale)	780
Red Bed	1050
Anhydrite	1075
Shells & Shale	1175
Shale & Lime Shells	1785
Shale & Lime	2050
Lime	2575
Shale & Lime	2740
Shale	2875
Shale & Lime	3712
Lime	4046
Lime & Shale	4080
Lime	4157
Lime & Shale	4210
Lime & Cong.	4229
Cherty Lime	4330
Cong., Dolo, Viola	4376
Lime	4449
Chert, Shale	4526
Dolo.	4539

STATE OF KANSAS)  
RUSSELL COUNTY ) SS.

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING CO.

By *Eric Baker*

Subscribed and sworn to before me this 2nd day of July, 1956.

*Charles L. ...*  
Notary Public

My Commission Expires 6/17/58

PLUGGING  
FILE SEC 31 T 21 R 18W  
BOOK PAGE 74 LINE 27