

15.145.00085.0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pawnee County, Sec. 26 Twp. 21 Rge. 18 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner Musgrove Petroleum Corporation
Lease Name Caston Well No. #1
Office Address 518 Petroleum Building, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed September 14, 1953
Application for plugging filed September 13, 1953
Application for plugging approved September 13, 1953
Plugging commenced September 14, 1953
Plugging completed September 14, 1953
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes verbal

Name of Conservation Agent who supervised plugging of this well Warren H. Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4080 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	950'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug at 270' with 20 sacks cement.
Set top plug at 35' with 10 sacks cement

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Musgrove Petroleum Corporation,
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of August, 1953

My commission expires 9-24-56

Thelma S. Stumpe
Notary Public

24-7366-5 3-53-20M

PLUGGING
FILE SEC 26 T 21 R 18 W
BOOK PAGE 129 LINE 31

9-22-53

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: CASTON #1
 LOCATION: NE NE NW, Sec. 26-21-18
 Pawnee County, Kansas.
 COMMENCED: Sept. 3, 1953
 COMPLETED: Sept. 14, 1953

0	30	Clay
30	40	Sand
40	110	Shale & clay
110	320	Shale & Post Rock
320	495	Blue shale
495	1535	Shale & shells
1535	1850	Shale, shells & sand
1850	1980	Shale & lime
1980	2095	Lime
2095	3560	Lime & shale
3560	3780	K. C. Lime
3780	3958	Lime
3958	3979	Cong.
3979	4080	Arbuckle
	4080	Rotary Total Depth

Set 8-5/8" surface casing at 950' with 450 sacks of cement.

Dry and abandoned.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the Caston #1, NE NE NW Section 26-21-18, Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY *Gordon L. Koelling*
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 21st day of September, 1953.

William L. Stumpe
 Notary Public

My commission expires September 24, 1956.

PLUGGING
 FBI SEC 26 T 21 R 18W
 BOOK PAGE 129 LINE 31