


15.145.00135.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 19 Twp. 21S Rge. 18 (E) (W)
Location as "NE/CNWxSWx" or footage from lines NE NE SW
Lease Owner Welch & Olsson Drilling Company, Inc.
Lease Name Wagner Well No. 1
Office Address 203 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-15 19 56
Application for plugging filed 12-14 19 56
Application for plugging approved 12-14 19 56
Plugging commenced 12-15 19 56
Plugging completed 12-15 19 56
Reason for abandonment of well or producing formation No commercial shows of oil and/or gas.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4365 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Filled hole with drilling mud to 370', set bottom plug, topped with 1/3 sack hulls and 20 sacks cement. Mud to 35', plug, 1/3 sack hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wilkinson Drilling, Inc.
Address 1111 Union National Building - Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Walter M. Wilkinson (~~employee of owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter M. Wilkinson
1111 Union National Bldg., Wichita 2, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of December, 19 56

My commission expires July 28, 1958.

Charles W. Barlow
Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 19 T. 21 R 18w
BOOK PAGE 126 LINE 29

DE 21
CONSERVATION DIVISION
Wichita, Kansas
12-21-56

WAGNER #1

Company - Welch & Olsson Co., Inc.
 Contractor - Wilkinson Drilling, Inc.
 Commenced - 12-3-56
 Completed - 12-15-56
 Init. Prod. - D & A

Location: NE NE SW, Sec. 19-21S-18W,
 Pawnee County, Kansas
 Elevation: 2076 DF
 Casing: 1185' - 8 5/8"

FIGURES INDICATE BOTTOMS OF FORMATION:

Depth	Formation
0 - 215	Sand & Shale
215 - 535	Clay & Shale
535 - 625	Shale w/Sand Strks.
625 - 760	Sand
760 - 1035	Shale & Red Beds
1035 - 1179	Shale, Red Beds & Shells
1179 - 1208	Anhydrite
1208 - 1980	Shale & Shells
1980 - 2078	Shale & Lime
2078 - 2315	Lime
2315 - 2460	Lime & Shale
2460 - 2550	Lime
2550 - 2765	Lime & Shale
2765 - 3240	Shale & Lime
3240 - 3585	Lime & Shale
3585 - 4185	Lime
4185 - 4248	Conglomerate
4248 - 4365	Lime
4365 - T. D.	

We hereby certify the above and foregoing to be a true and correct copy of the log on the Wagner #1, located in the NE NE SW, of Section 19-21S-18W, Pawnee County, Kansas.


WILKINSON DRILLING, INCORPORATED

Walter M. Wilkinson

Subscribed and sworn to before me this 18th day of December, 1956.

Charlene Barchus
 Notary Public

My commission expires July 28, 1958



VED
 DIVISION
 DIVISION DIVISION
 Wichita, Kansas