

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

*J. Lewis Brock*J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION
NOV 30 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 200 West Douglas Wichita, Kansas 67202

Lease Name Petro Well No. 1

Location SW NW SE Sec. 29 Twp. 23 Rge. (E) (W) 15

County Pawnee Total Depth 4109'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 3 P Day 24 Month 11 Year 1970

The Above well was plugged as follows:

Total Depth 4109' 8 5/8 csg set at 208' cwc 200 sk.

5 1/2 csg set at 4105' cwc 860 sk cmt.

5 1/2 csg PBTD 2624' with top perf. (2586')

Filled 5 1/2 csg W/sd (2560-2624) Dumped 5 sk cmt W/dump bailer. (2520-2560)

Cutoff and recovered 2300' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/3 sk hulls, plug and 100 sk reg poz.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Mursing
Well Plugging SupervisorDATE 12/1/70INV. NO. 2933-u