

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Thomas H. Allar

Complete Address: R. R. #1 Great Bend, Kansas 67530

Lease Name Becker Well No. C-1

Location SE SW SW Sec. 29 Twp. 23 Rge. 15 (E) (W) X

County Pawnee Total Depth 4155

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 3 P Day 20 Month 8 Year 1968

The Above well was plugged as follows:

Total Depth 4155' 8 5/8 csg set at 418' cwc 250 sc.

5 1/2 csg set at 4154' cw 175 sc.

5 1/2 csg PBTD 4143' with top perf. at 4067'

5 1/2 csg filled with sand (4155-4000) and dumped 5 sc cement with dump bailer (4000-3960)

Cutoff 5 1/2 csg at 2100'.

Pumped 40 sc cmt. to 2000'.

Cutoff and recov. 1830' of 5 1/2 csg.

Set rock bridge (375-350) and dumped 5 sc cmt. with dump bailer. (350-340)

Filled to surface with 5 yds. readymix cmt. (340-0)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Murray
Well Plugging Supervisor

DATE 8/23/68

INV. NO. 8327-4