

SP

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth Nat'l Bank Bldg., Wichita, Kansas

Lease Name Reece "B" Well No. 1

Location C NW NW Sec. 17 Twp. 21 Rge. 19 (E)    (W) X

County Pawnee Total Depth 4310'

Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X

Other well as hereafter indicated:   

Plugging Contractor:    Co. Tools   

Address:    License No.   

Operation Completed: Hour 8:45 A Day 12 Month 2 Year 1968

The Above well was plugged as follows:

RTD 4310' 8 5/8 csg set at 274' cwc 180 sc. Cem. Mat. 100 sc cement W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 sc cem.

thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plud, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 15 1968

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 2-15-68

INV. NO. 7270-W