

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 16 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Robert R. Price and Aspen Drilling Co.

Complete Address: ~~Box~~ Tulsa, Oklahoma 5727 E. 43rd 74135

Lease Name Darnall Well No. 1

Location SE SE Sec. 4 Twp. 21 Rge. 19 (E) (W) XX

County Pawnee Total Depth 4386'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Gabbert & Jones Drlg.

Address: Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 11A Day 15 Month 12 Year 1968

The Above well was plugged as follows:

RTD 4386' 8 5/8 csg set at 422' cwc 200 sc. Cmt. Mab. 50-50 poz cmt. W/6% total gel  
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 50 sc cmt.  
thru drill pipe. Heavy mud to 390' set cementing plug and displaced 25 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/17/68  
INV. NO. 9041-W

Signed: Geo F. Massey  
Well Plugging Supervisor