

KANSAS

FORM CP-3
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-145-20,322 ✓

245 North Water
Wichita, KS 67202

Operator's Full Name INTERNORTH, INC.

Complete Address P.O. BOX 25288 - TULSA, OKLAHOMA, 74135

Lease Name MURPHY Well No. #1-23

Location SW-NE-NE Sec. 23 Twp. 21 Rge. 18 (East) (West)

County PAWNEE Total Depth 2156 ^{EE}

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor SUN OIL WELL CEMENTING

Address BOX 169 GREAT BEND, MS. License No. _____

Operation Completed: Hour: 11:45 ^{AM} Day: 27 Month: JAN Year: 19 81

The above well was plugged as follows:

8 5/8" 812 ^{EE} SB. CMC / 275 ST CMT. → 4 1/2" SET @ 2156 ^{EE} / 125 ST CMT.

PLUG. BACK. 2082 ^{EE} → PERFS - 2046' - 2052' + 2066' - 2076'.

STAGING COLLOR AT. 1123 ^{EE} STAGED THREE TIMES / 550 ST CMT.

ORDERED - 105 ST 50/50 Pozmix - 6% GEL. → 1 ST HULL'S → 4 1/2" PLUG.

PUMPED IN WITH PUMP TRUCK. - NO PIPE RECOVERY. - ANNULUS CMC.

PUMPED IN 4 1/2" - 1 ST HULL'S → 55 ST CMT. → RELEASED PLUG.

AND 50 ST CMT. MAX. PRESSURE 400 ^{PSI}

CEMENTED BY SUN OIL WELL CEMENTING

JAN 28 1981
1-28-1981
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 2-9-81

INV. NO. 4486-U