

15.075-30020-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1967
2-20-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Livingston Oil Company

Complete Address: Box 1797, Tulsa, Oklahoma

Lease Name Unit 3511-B Well No. 3511-B

Location C NW SE Sec. 35 Twp. 21 Rge. 41 XK (W)

County Hamilton Total Depth 2772'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 6:30PM Day 17 Month 2 Year 1967

The Above well was plugged as follows:

8 5/8" to 169' circulated w/ cement. 4 1/2" to 2772' cemented.

Top perforations 2744' Plug bottom w/10 sacks cement

Top of cement 2640' Mud 2640' to 600'

Spotted 25 sacks cement 600' to 500' Mud 500' to 170'

Spotted 20 sacks cement 170' to 110' Mud 110' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'. Company Pump

Pulled 2221' of 4 1/2" casing 42"

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edward J. Eves
Well Plugging Supervisor

DATE 2-20-67

INV. NO. 4791-w