

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW - NE/4

SEC. 1 TWP. 21 RGE. 18-W

Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 1 Lease English

Operator Mr Max Cohen Address #203 - Brown Bldg. Wichita - Kas.

Field _____ County Rawl

Total Depth 3658 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 5/8 - 870 ft. Circulated with cement
5 1/2 casing set at 3657 ft. - 100 sacks of cement.
Plugged back to 3446 ft. with Lane Wells Plug - mud
x back - Pumped 8 sacks of cement at 3446 ft. - Shot
off & killed the 5 1/2 casing - Pumped in 100 sacks of
baroid Mud - Set Rock Bridge x 20 sacks of cement
at 250 ft - mud to 30 ft - Bridge x 5 sacks of
cement at the surface.

PLUGGING
FILE SEC 1 T 21 R 18W
BOOK PAGE 39 - LINE 35

C. H. Stough
District Conservation Agent

Date 1-20-52

1-23-52 JAN 23 1952