

KANSAS

STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 3 1972

CONSERVATION DIVISION  
 Wichita, Kansas

J. Lewis Brock  
 Administrator  
 P. O. Box 17027  
 Wichita, Kansas 67217

Operator's Full Name Joe Brougher  
 Complete Address 8513 Apache Great Bend, Kansas 67530  
 Lease Name Weathers Well No. 1  
 Location Se/4 Sec. 1 Twp. 21 Rge. (E) (W) 15  
 County Pawnee Total Depth 3746'  
 Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
 Other well as hereafter indicated         
 Plugging Contractor Russ Casing Pulling  
 Address Box 1082 Great Bend, Kansas License No. 623  
 Operation Completed: Hour 9:1A Day 1 Month 7 Year 1972

The above well was plugged as follows:

Total Depth 3746' 8 5/8 csg set at 879' cwc 400 sk

5 1/2 csg set at 3745' cw 150 sk cmt.

Filled 5 1/2 csg W/sd (3700-3746) Dumped 5 sk cmt W/dump bailer. (3685-3700)

Cutoff and recovered 2700' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released 8 5/8 plug  
 and pumped 100 sk 50-50 poz cmt W/6% total gel. by HOWCO.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
 Well Plugging Supervisor

DATE 7-5-72  
 INV. NO. 5981-W