

*R*

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 28 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Isern - Herbel

Complete Address Box 486 Ellinwood, Kansas 67526

Lease Name Hurr Well No. # 4

Location C SE SW Sec. 18 Twp. 21 Rge. 7 (E) (W)

County Rice Total Depth 3378'

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Pipe Pullers Inc.

Address Ellinwood, Kansas License No. # 462

Operation Completed: Hour 5 PM Day 26 Month 8 Year 70

The above well was plugged as follows:

8 5/8"-271'-Circulated w/cement. 5 1/2"-3377'-Cemented. Sand to 3370'.  
5 Sax.cement 3370' to 3330'. Mud 3330' to 290'. Bridge 290' to 280'.  
25 Sax.cement 280' to 210'. Mud 210' to 40'. Bridge 40' to 30'.  
10 Sax.cement 30' to 0. Pulled 2209'-5 1/2"-Pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Hugh Scott*  
Well Plugging Supervisor

DATE 8-28-70

INV. NO. 2446-W