



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

2-21-75 Feb 21 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Isern Petroleum Company

Complete Address Box 486, Ellinwood, Kansas 67526

Lease Name McCrorry Well No. 3

Location C SE NE Sec. 18 Twp. 21 Rge. 7 (E) (W) X

County Rice Total Depth 3360'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour Noon Day 11 Month February Year 1975

The above well was plugged as follows:

Hole filled with sand to 3300' and cemented with 5 sacks cement.

Hole bailed to 210'. Rock bridge set from 210' to 200' and hole

cemented with 35 sacks cement. Hole filled with mud to 40'. Rock

bridge set from 40' to 30' and hole cemented to base of cellar with

10 sacks cement.

2920' of 5 1/2" casing recovered.

I hereby certify that the above well was plugged as herein stated.

Signed:
Well Plugging Supervisor

INVOICE #

DATE 2/21/75

INV. NO. 352-W