

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Intent to Drill,  
filed July 31, 1967.

RECEIVED  
AUG 9 1967  
8-9-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Aspen Drilling Company

Complete Address P. O. Box 783, Great Bend, Kansas 67530

Lease Name Wolf Well No. # 3

Location NW SW SE Sec. 3 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3562'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Aspen Drilling Company

Address P. O. Box 783, Great Bend, Kansas 67530 License No.     

Operation Completed: Hour 6:30 P.M. Day 7th Month August Year 1967

The above well was plugged as follows:

246' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid level  
in the hole was at 145'. 1st cementing plug and 1/4 sack of hulls was pushed  
in fluid to 240', and cemented with 25 sacks, through the drill pipe, with  
cement from 240' to 165'. Hole was filled with drilling mud to 40', 2nd  
cementing plug, bridged with 1/2 sack of hulls on fluid at 40', and cemented  
with 10 sacks from 30' to the base of the cellar. Rat hole bridged and cem-  
ented with 3 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving  
Well Plugging Supervisor

INVOICED

DATE 8/9/67

INV. NO. 6104-u