

15.185.19470.0000

Form CP-3
Rev. 6-26-62

16
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 4 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name S. A. Murphy

Complete Address: 712 Brown Bldg., Wichita, Kansas

Lease Name Ferris-Salem Well No. # 2

Location C SW SE SE Sec. 8 Twp. 21 Rge. 12 (E) (W)W

County Stafford Total Depth 3515'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Virginia Drilling Company Inc.

Address: 712 Brown Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 11:00AM Day 3rd Month Nov. Year 1964

The Above well was plugged as follows:

275' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid
level in the hole was at 65'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 260', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged and
cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/4/64

INV. NO. 111-2