

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1967
2-10-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued January 18, 1967.

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 410 Fouth National Bank Bldg., Wichita, Kansas

Lease Name Wolf Well No. # 1

Location NE NW SE Sec. 32 Twp. 21 Rge. 11 (E) (W)W

County Stafford Total Depth 3550'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Bert Self Casing Pulling Company

Address: R. R. # 4, Hutchinson, Kansas License No. 48

Operation Completed: Hour 3:15PM Day 7th Month Feb. Year 1967

The Above well was plugged as follows:

253' of 8 5/8" surface pipe, cemented with 250 sacks. 3549' of 5 1/2" long
string, cemented with 200 sacks. This is an open hole. Bottom of the hole
was sanded to 3525', and cemented with 5 sacks, through the dump bailer.
2300' of 5 1/2" long string was recovered from the hole. Hole was flowing
with water and a squeeze job was necessary. A short 5 1/2" nipple was packed
in the braden head. 10 sacks of Gel-Mud and 80 sacks of cement was pumped
in the 5 1/2" nipple, through a 5 1/2" swage, to a pressure of 200 lbs., bringing
the cement to the base of the cellar. This cement was pumped by Halliburton
Cementing Company.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED
DATE 2/10/67
INV. NO. 4743-11