

15.185.19469.0000

Form CP-3  
Rev. 6-26-62

 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

MAR 23 1966  
3-28-66  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Wolf Well No. # 2

Location C SE NW SE Sec. 32 Twp. 21 Rge. 11 (E) W

County Stafford Total Depth 3515'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 2:00PM Day 25th Month March Year 1966

The Above well was plugged as follows:

256' of 8 5/8" surface pipe, cemented with 160 sacks. 3510' of 5 1/2" long  
string, cemented with 125 sacks. Plug back T.D. 3509'. Top perforation  
3440'. Bottom of the hole was sanded to 3400', and cemented with 5 sacks,  
through the dump bailer. 2450' of 5 1/2" long string was recovered from the  
hole. Hole was flowing with water and a squeeze job was necessary. 10 sacks  
of Gel-Mud and 80 Sacks of cement was pumped into the surface pipe, through  
8 5/8" swage to a pressure of 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 3-28-66

INV. NO. 2930-W