

15.185.19467.0000

Form CP-3  
Rev. 6-26-62

*Y* KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 14 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name F. G. Holl

Complete Address: 6427 East Kellogg, Wichita, Kansas

Lease Name Fair "B" Well No. # 2

Location SW NW NW Sec. 23 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3442'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Duke Drilling Company

Address: Box 823, Great Bend, Kansas License No.     

Operation Completed: Hour 12:30PM Day 9th Month Nov. Year 1966

The Above well was plugged as follows:

255' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fluid  
level in the hole was at 95'. 1st cementing plug and 1/2 sack of hulls  
was pushed in fluid to 240', and cemented with 25 sacks. through the  
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid  
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole  
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 11/15/66  
INV. NO. 4284-11