

State of Kansas



15.185.20014.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS-67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 6 1967  
3-6-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill, filed  
February 27, 1967.

Dear Sir:

Mr. Larry Curtis of Duke Drilling Company has this date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: F. G. Holl

Complete Address: 6427 E. Kellogg, Wichita, Kansas

Lease Name: Gilchrest Well No. # 1

Location: SE SE SW Sec. 12 Twp. 21 Rge. 11(E) (W) W

County Stafford Total Depth 3432' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Curtis was instructed to plug the well as follows:

253' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill hole with drilling mud to 230', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Audie Elving  
Conservation Division Agent