



15.083.20040.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 29 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Fannenstiel of Tilco has this

date requested permission to plug the following described well:

Mr. Fannenstiel guarantees payment of the plugging fee.

Operator's full Name: Tilco et al

Complete Address: 815 Wichita Plaza, Wichita, Kansas

Lease Name: Waterhouse Well No. 1

Location: 150' SE C SW NE Sec. 12 Twp. 21 Rge. 23 (W)

County Hodgeman Total Depth 4520' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Fannenstiel was instructed to plug the well as follows:

8 5/8" to 424' circulated w/ cement. Mud 4520' to 1150'

Spotted 100 sacks cement 1150' to 800' Mud 850' to 424'

Spotted 30 sacks cement 424' to 324' Mud 324' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Eves  
Conservation Division Agent