

State of Kansas



15.185.20049.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed July 31, 1967.

Dear Sir:

Mr. Bill Schachle of Aspen Drilling Company has this date requested permission to plug the following described well:

Mr. Schachle guarantees payment of the plugging fee.

Operator's full Name: Aspen Drilling Company

Complete Address: P. O. Box 783, Great Bend, Kansas 67530

Lease Name: Wolf Well No. # 3

Location: NW SW SE Sec. 3 Twp. 21 Rge. 12 (E)(W) W

County Stafford Total Depth 3562' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Schachle was instructed to plug the well as follows:

246' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlie Elving
Conservation Division Agent