

State of Kansas



FORM - CP-2
Rev. 6-26-62

15.185.19470-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1964
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Clayton Hooper of Virginia Drilling Co., Inc has this date requested permission to plug the following described well:

Mr. Hooper guarantees payment of the plugging fee.

Operator's full Name: S. A. Murphy

Complete Address: 712 Brown Bldg., Wichita, Kansas

Lease Name: Ferris-Salem Well No. # 2

Location: C SW SE SE Sec. 8 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3515 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hooper was instructed to plug the well as follows:

275' of 8 5/8" surface pipe, cement circulated with 250 sacks.
Fill hole with drilling mud to 260', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving