



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission  
 CONSERVATION DIVISION  
 (Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 19 1962

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Ralph Schuyler of Strata Drilling Inc. has this

date requested permission to plug the following described well:

Mr. Ralph Schuyler guarantees payment of the plugging fee.

Operator's full Name: Kansas Petro. Inc.

Complete Address: 720 <sup>Bitting</sup> Britting Bldg. Wichita Kansas

Lease Name: Manning Well No. #1

Location: C -SE - NE Sec. 29 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3488 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Schuyler was instructed to plug the well as follows:

284' of 8 5/8" surface pipe circulated with cement. Hole was

filled to 280' with heavy drill mud, 1/4 sack hulls, ~~1~~ 1 st

plug was cemented through drill pipe with 25 sacks. Hole

filled to 40' with heavy drill mud, 1/2 sack hulls, 2 nd cement-  
ing plug, 10 sacks cement to base cellar. Rat hole bridged

and two sacks cement

Very truly yours,

Archie Elving  
 Conservation Division Agent