

State of Kansas



15.185.20277-0000

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gustus of Leben Drlg. Co. Inc. has this
date requested permission to plug the following described well:

Mr. Gustus guarantees payment of the plugging fee.

Operator's full Name: Leben et al

Complete Address: 200 W. Douglas Wichita, Ks

Lease Name: Smith Well No. 3

Location: 0 E/2 NE Sec. 29 Twp. 21s Rge. 11 (E)(W) W

County: Stafford Total Depth 3473 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gustus was instructed to plug the well as follows:

475 ft of 8 5/8 surface pipe cemented with 350 sacks.

Fill hole to 550 ft, plug, 35 sacks cement. Plug at 400 ft.

25 sacks cement. Mud to 40 ft, 1/2 sack hulls, plug, 10

sacks cement to surface. 2 sacks cement in rat hole.

Very truly yours,

L. Russell Biberstein
Conservation Division Agent