



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 2 1963

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

12-2-1963

Dear Sir:

Mr. Doyle Rand of Harms Drilling Co. has this

date requested permission to plug the following described well:

Mr. Rand guarantees payment of the plugging fee.

Operator's full Name: H. C. Bennett & Harms Drilling Co.

Complete Address: Box 488, Great Bend, Kansas

Lease Name: Eriksen Well No. # 1

Location: S/2 SW SE Sec. 34 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3525 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rand was instructed to plug the well as follows:

286' of 8 5/8" surface pipe, cemented 250 sacks. Fill  
hole with drilling mud to 275', 1st cementing plug, 1  
sack hulls, cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, cement with 10 sacks to  
base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent