

State of Kansas



15-185-30270-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Max Lattimer of Raymond Oil Co., Inc. has this date requested permission to plug the following described well:

Mr. Lattimer guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Inc.

Complete Address: 410 Fourth National Bank Bldg., Wichita, Kansas

Lease Name: Rugan Well No. # 1

Location: SW NW SW Sec. 22 Twp. 21 Rge. 11 (E)(W) W

County Stafford Total Depth 3402' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Lattimer was instructed to plug the well as follows:

205' of 10, 3/4" surface pipe, cement circulated with 325 sacks. Fill hole with drilling mud to 200', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 30 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 15 sacks to base of well. Bridge and cement rat hole with 2 sacks.

STATE CORPORATION COMMISSION

MAY 26 1966

CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

Aubrey Ewing  
Conservation Division Agent