

State of Kansas



FORM - CP-8
Rev. 8-28-62

15.185-30180-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 16 1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

11-16-1964

Mr. Howard Roberts of Strata Drilling Inc. has this
date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: Time Petroleum Company

Complete Address: 815 Union National Bldg., Wichita, Kansas

Lease Name: Meier Well No. # 1

Location: SW NW SW Sec. 22 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3740 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Roberts was instructed to plug the well as follows:

272' of 8 5/8" surface pipe, cement circulated. Fill hole
with drilling mud to 260', 1st cementing plug, bridge with
hulls, and cement with 25 sacks, Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and
cement with 10 sacks to base cellar. Bridge and cement rat
and mouse hole with 5 sacks.

Very truly yours,
Archie Elving