


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15.185.00866.0000
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

STAFFORD County. Sec. **11** Twp. **21S** Rge. **11 W** (E) X (W)
Location as "NE/CNW%SW%" or footage from lines **NE NW SW**
Lease Owner **PETROLEUM, INC.**
Lease Name **SCHAFFER** Well No. **1**
Office Address **ROUTE 2, GREAT BEND, KANSAS**
Character of Well (completed as Oil, Gas or Dry Hole) **DRY HOLE**
Date well completed **NOVEMBER 22, 19 58**
Application for plugging filed **NOVEMBER 22, 19 58**
Application for plugging approved **NOVEMBER 21, 19 58**
Plugging commenced **NOVEMBER 21, 19 58**
Plugging completed **NOVEMBER 22, 19 58**
Reason for abandonment of well or producing formation **NO PRODUCIBLE ZONES**

If a producing well is abandoned, date of last production **NONE** 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **YES**

Name of Conservation Agent who supervised plugging of this well **FRANK BROADFOOT, 222 SOUTH MAIN, ST. JOHN, KANS.**
Producing formation _____ Depth to top **--** Bottom **--** Total Depth of Well **3425** Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	262.48	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUD UP WITH HEAVY MUD TO 240', PUSHED DOWN 1/4 SACK HULLS TO 240' FOLLOWED BY WOODEN PLUG. PLACED 20 SACKS CEMENT THROUGH DRILL PIPE ON TO PLUG. MUD UP TO 35' AND PLACED 1/4 SACK HULLS TO 35' FOLLOWED BY WOODEN PLUG AND 10 SACKS CEMENT TO BASE OF WELL CELLAR.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor **GARVEY DRILLING COMPANY**
Address **ROUTE 2, GREAT BEND, KANSAS**

STATE OF **KANSAS**, COUNTY OF **BARTON**, ss.
DON SEARLE (employee of owner) or ~~(owner)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Don Searle*
ROUTE 2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this **29TH** day of **NOVEMBER**, 19 **58**

My commission expires **JULY 11, 1960**

STATE CORPORATION COMMISSION Public

PLUGGING
FILE SEC. **11** T. **21** R. **11W**
BOOK PAGE **148** LINE **37**

DEC 1 - 1958
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

15.185.00866.0000

COMPANY PETROLEUM, INCORPORATED

SEC. 11 T. 21S R. 11W

FARM SCHAFFER NO. 1


LOC. NE, NW, SW

TOTAL DEPTH 3425'

COUNTY STAFFORD CO., KANSAS

COMM. November 13, 1958 COMP. November 22, 1958

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 262.48' W/225 sax.

ELEVATION 1753' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

160	Surface soil & sand
265	Red bed & shale
448	Red bed
480	Anhydrite
1215	Shale & shells
1708	Lime & shale
2010	Lime
2235	Lime & shale
2640	Shale w/lime streaks
2718	Lime
2868	Shale & lime
2944	Lime
3069	Lime & shale
3327	Lime
3405	Cherty lime
3425	Lime
3425	T. D.

PLUGGING
 FILE SEC. 11 T. 21 R. 11W
 BOOK PAGE 148 LINE 37

State of KANSAS }
 County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 SCHAFFER well

Subscribed and sworn to before me this 28th day of November 19 58

My Commission Expires: July 11, 1960

Verne A. Morris
 RECEIVED
 STATE CORPORATION COMMISSION
 DEC 1 - 1958
John T. Brown
 NOTARY PUBLIC
 Wichita, Kansas