

STATE OF KANSAS
STATE CORPORATION COMMISSION
290 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15 - 185-22,687.0000

LEASE NAME Schafer

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2-11

4860
4620 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR F. G. Holl Company

SEC. 11 TWP. 21 SRGE. 11W (E or W)

ADDRESS P. O. Box 780167
Wichita, Kansas 67278-0167

COUNTY Stafford

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Date Well Completed 6-24-90

Character of Well Dry Hole

3:00 AM,

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Commenced 6-24-90

4:15 AM,

Plugging Completed 6-24-90

The plugging proposal was approved on June 23, 1990 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filled? _____ If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3375'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	277'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Filled hole with heavy mud. Plugged with 50 sacks at 550'; 50 sacks at 300';
15 sacks at 60'; 15 sacks in rathole. Used 60/40 Pozmix with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129
Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard L. Mead
Richard L. Mead, President
(Address) P. O. Box 129, Sterling, Kansas 67579

RECEIVED
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION
6-27-90

JUN 27 1990

SUBSCRIBED AND SWORN TO before me this 26th day of June, 1990

CONSERVATION DIVISION
Wichita, Kansas

Agnes D. Wurst
Agnes D. Wurst, Notary Public

My Commission Expires: 4-26-93



STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - SCHAFFER #7-11

Located: 240' North of C W/2 NW NW, Section 11-21S-11W,
Stafford County, Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 18, 1990

COMPLETED: June 24, 1990

TOTAL DEPTH: 3375'

LOGCASING RECORD

0 - 180 Sand and Clay
180 - 280 Red Bed
280 - 1320 Red Bed, Shale
1320 - 3375 Lime and Shale

Ran 6 joints 8 5/8" casing. 264.87'
pipe set at 277' K.B. Cemented with
225 sacks 60/40 Pozmix with 2% gel
and 3% cc. Plug down at 11:45 AM,
6-18-90, by B. J. Titan.

Plugged.

Deviation Survey: 3/4° at 3120'