

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-185-23115-0000
LEASE NAME McFarland
WELL NUMBER A' 1-11

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

840 Ft. from South Line of Section
1950 Ft. from West Line of Section

LEASE OPERATOR F.G. Holl Company, L.L.C. SPOT LOCATION 150'S & 30' E of N/2 SW SE of
ADDRESS P.O. Box 780167 Section 11 Township 21s Range 11w
CITY, STATE, ZIP Wichita, Kansas 67278-0167 County Stafford
PHONE # 316-684-8481 Date Well Completed November 21, 20
Character of Well Dry and Abandoned Date Plugging Commenced November 21, 20
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed November 22, 20

The plugging proposal was approved on November 21, 2000 at 9:20 am. (date)
by Steve Middleton (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 3575

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	140	and		
Redbeds	Shale	140	240	8-5/8"	225.96	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well as follows using 155 sacks 60/40 Poz 6% Gel: Began plugging at 11:00 pm on 11-21-00.

Heavy mud from 3575' to 3440' then 40 sx, heavy mud to 450' then 40 sx, heavy mud to 260' then 40 sx, heavy mud to 40' then 10 sx, cement did circulate, 15 sx rathole, 10 sx mousehole.

Plugging completed at 12:30 am on 11-22-00 by Acid Services ticket # 02750.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company, L.L.C. (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.

Gary Talbott, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.


(Signature) *Gary M. Talbott*
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 22nd day of Nov., 192000

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 2000



Pamela S. Fields
(Notary Public)

CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires: _____

Form CP-4
Revised 12-92
MB

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG**McFarland A' 1-11**

LOCATION: 150'S & 30' E of N/2 SW SE of
API: 15-185-23115-0000

Section 11 T 21s R 11w
Stafford County, Kansas

OWNER: F.G. Holl Company, L.L.C.
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 15-Nov-00
COMPLETED: 22-Nov-00

TOTAL DEPTH: **DRILLER** 3575 FEET
LOGGER 3442 FEET

Ground Elevation: 1735
KB Elevation: 1744

LOG

0 -	185 FEET	Top Soil and Sand
185 -	442 FEET	Shale and Redbeds
442 -	470 FEET	Anhydrite
470 -	3502 FEET	Limestone, Shale and Dolomite
3502 -	3575 FEET	Arbuckle

CASING RECORDS**Surface Casing**

Spud @ 9:00 am on 11-15-00. Drilled 12-1/4" hole to 240'. Ran 5 joints of new 23# 8-5/8" surface casing 225.96' set at 237' KB. Cemented with 225 sacks 60/40 Poz, 2% Gel, 3% CC, Plug down at 12:45 pm on 11-15-00 by Acid Services. Ticket #02677. Cement did circulate.

Plugging Report

Plugged well as follows using 155 sacks 60/40 Poz 6% Gel: Began plugging at 11:00 pm on 11-21-00. Heavy mud from 3575' to 3440' then 40 sx, heavy mud to 450' then 40 sx, heavy mud to 260' then 40 sx, heavy mud to 40' then 10 sx, cement did circulate, 15 sx rathole, 10 sx mousehole. Plugging completed at 12:30 am on 11-22-00 by Acid Services ticket # 02750.

DEVIATION SURVEYS

3/4 degree(s) at	240	feet
1 1/4 degree(s) at	3345	feet

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 2000

CONSERVATION DIVISION
Wichita, Kansas