

RECEIVED

OCT 15 2001

KCC WICHITA  
TYPE OR PRINT

Well Plugging Record  
K.A.R. -82-3-117

10-15-01

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-185-23140-0000  
LEASE NAME Gilchrist  
WELL NUMBER 1-12

NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

2240 Ft. from South Line of Section  
1070 Ft. from West Line of Section

LEASE OPERATOR F.G. Holl Company, L.L.C. SPOT LOCATION 70' S & 80' E of Ne Nw Sw  
ADDRESS P.O. Box 780167 Section 12 Township 21s Range 11w  
CITY, STATE, ZIP Wichita, Kansas 67278-0167 County Stafford  
PHONE # 316-684-8481 Date Well Completed October 11, 2001  
Character of Well Dry and Abandoned Date Plugging Commenced October 11, 2001  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed October 11, 2001

The plugging proposal was approved on October 11, 2001 at 11:45 am (date)  
by Jim Holland (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 3500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	88			
Redbeds	Shale	88	230	8-5/8"	213.99'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged well on 10/11/01 using 150 sx 60/40 Poz, 6% Gel, as follows: Heavy mud in the hole.

Bottom plug @ 3460' with 40sx, 2nd plug @ 600' with 50sx, 3rd plug @ 240' with 50sx

and top plug @ 40' with 10sx cemented to surface, Plugged rathole with 15 sx. No mousehole.

Plug down at 11:30 am on 10/11/01 by Acid Services, ticket #4188.

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company, L.L.C. (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first  
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of  
the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott  
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 12th day of October, 2001



Pamela S. Fields  
(Notary Public)

My Commission Expires:

Form CP-4  
Revised 12-92

R  
OR

RECEIVED

OCT 15 200

KCC WICHITA

**Sterling Drilling Company, Rig #1**

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (316) 672-9508, Fax 672-9509

**SAMPLE LOG**

**Gilchrist 1-12**

**LOCATION:** 70' S & 80' E of Ne Nw Sw Section 12 T 21s R 11w  
**API:** 15-185-23140-0000 Stafford County, Kansas

**OWNER:** F.G. Holl Company, L.L.C.  
**CONTRACTOR:** Sterling Drilling Company, Rig #1

**COMMENCED:** 04-Oct-01  
**COMPLETED:** 11-Oct-01

**TOTAL DEPTH:** **DRILLER** 3500 FEET  
**LOGGER** 3502 FEET

**Ground Elevation:** 1738  
**KB Elevation:** 1747

**LOG**

0 -	3 FEET	Top Sand
3 -	18 FEET	Sand and Gravel
18 -	32 FEET	Clay
32 -	55 FEET	Fine Sand
55 -	80 FEET	Sand and Gravel
80 -	478 FEET	Shales
478 -	490 FEET	Anhydrite (Driller's)
490 -	1325 FEET	Redbeds, Shales and Salt
1325 -	3460 FEET	Limestone, Shale and Dolomite
3460 -	3500 FEET	Arbuckle

**CASING RECORDS**

**Surface Casing-8-5/8"**

Spud @ 10:00 am on 10/04/01. Drilled 12-1/4" hole to 230'. Ran 5 joints of new 23# 8-5/8" surface casing, tally 213.79' set at 225' KB. Cemented with 225 sx 60/40 Poz, 2% Gel, 3% CC and 1/4# Celloflake. Cement did circulate. Plug down at 3:45 pm on 10/04/01 by Acid Services.

**Plugging Report**

Plugged well on 10/11/01 using 150 sx 60/40 Poz, 6% Gel, as follows: Heavy mud in the hole. Bottom plug @ 3460' with 40sx, 2nd plug @ 600' with 50sx, 3rd plug @ 240' with 50sx and top plug @ 40' with 10sx cemented to surface, Plugged rathole with 15 sx. No mousehole. Plug down at 11:30 am on 10/11/01 by Acid Services, ticket #4188.

**DEVIATION SURVEYS**

1-3/4 degree(s) at 230 feet  
1-1/2 degree(s) at 2648 feet